

BILLS OF QUANTITY

1 Tender Inviting Authority-	Block Development Officer Daringbadi
2 NAME OF THE WORK:-	Construction of Additional Building at Daringbadi Block under Daringbadi Block in the district of kandhamal for the year 2022-23.
3 Estimated Cost	Rs-30,00,000/-(Rupees Thirty Lakh)only
4 Tender Amount	Rs.24,59,651/-
5 E.M.D Required	Rs.24,597/-
6 Cost of Tender Paper	Rs-6,000/-(Six Thousand)only
7 Class of Contractor	C and B
8 Time of Completion	06(Six)Calender Months
9 Last date of Sale of Tender Paper	06.03.2023
10 Last date of Received of Tender Paper	06.03.2023(Up to 2.00pm)
11 Date of Opening of Tender Paper	06.03.2023(at 4.00pm)at Block Office

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	AMOUNT (In Rs)
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	61.49	Cum	196.81	12102.00
2	Filling foundation and plinth with good coarse sand including watering & ramming as directed by the Engineer in charge.	51.87	Cum	799.68	41479.00
3	Cement Concrete M10(1:3:6) with 4cm size hard granite metal including cost, conveyance, royalty, taxes, watering and curing etc. complete.	26.33	Cum	4753.75	125166.00
4	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In foundation)	13.60	Cum	4094.98	55692.00
5	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying	62.90	Cum	5741.93	361167.00
6	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.(Ground Floor)	53.00	Qtl	9256.77	490609.00
7	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In foundation)	28.45	Cum	4365.52	124199.00
8	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying	44.44	Cum	5827.71	258983.00
9	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.(Ground Floor)	39.75	Qtl	9280.90	368916.00
10	20 mm thick cement plaster in cement mortar (1:6) out side/face brick walls etc complete.(Ground Floor)	255.32	Sqm	246.86	63028.00



	Rigid Smooth centering and shuttering for RCC work etc completed.				
11	Column Base				
12	Lintel	140.45	Sqm	106.27	14926.00
13	Column & Beam (GF)	16.83	Sqm	325.62	5480.00
14	Column & Beam (FF)	104.53	Sqm	750.41	78440.00
15	Chajja(GF)	104.53	Sqm	900.50	94129.00
16	Chajja (FF)	275.84	Sqm	528.60	145809.00
17	Roof Slab	255.32	Sqm	440.50	112468.00
18	Stair Case (GF)	29.40	Sqm	611.71	17984.00
19	16 mm thick cement plaster in cement mortar (1:6) out side/face brick walls etc complete.(Ground Floor)	29.40	Sqm	734.05	21581.00
20	12 mm thick cement plaster in cement mortar (1:6) out side/face brick walls etc complete.(Ground Floor)	192.29	Sqm	214.50	41246.00
		169.03	Sqm	155.28	26247.00
Total: 20 (Twenty Items)Only				CIVIL COST RS.	2459651.00

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage,Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials,Labour,Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST,Income Tax,Royalties,Labour Cess as applicable will be deducted from the bill of the Contractor.For all above works the minium grade of cement OPC,TMT High strength steel Fe-500.


Block Development Officer
Daringbadi Block

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____

_____ only(both in figures and words).

Signature of the Contractor