

Tender Inviting Authority: Block Development Officer, K.Nuagaon Dist-kandhamal.	
Name of the Project-New Construction of Culvert on the Road from (Kudutuli) Pipal Sahi to MIP Dam.	
Contract No:	
Bidder Name:	Excess (+) %

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Estimated	AMOUNT Rs. P
				Figure	
1	Earth work in excavation of foundation in hard or gravel soil with initial lead and lifts including dressing and leveling the bed and depositing the excavated earth at places away from work site with all leads and lifts including cost of all labour, cess and T&P and dewatering if required for the work etc. Complete as directed by the Engineer-in charge	136.83	One Cum	198.45	27154.00
2	Supplying & filling good clean river sand inside the foundation / plinth of approved area including watering to complete saturation & ramming complete with all leads & lifts including cost, conveyance, royalty, cess & taxes of all materials & cost of all labour & T&P required for the work complete (measurement will be taken for compacted section) as per direction of Engineer-in-Charge.	16.91	One Cum	293.04	4955.00
3	Cement Concrete of proportion (1:3:6) in foundation and floors using 4cm size clean hard black broken granite stone metal of approved quality and from approved quarry including hosting lowering and laying concrete in layers not exceeding 15cm thick to the required level ramming, watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour, cess with T&P required for the work etc. complete including dewatering if required as per direction of the EIC.	191.58	One Cum	4408.45	844571.00
4	RCC of design mix of M-20 grade of controlled quality having cube strength of 250kg./cm2 in design mix with minimum quantity of cement as specified in IRC Code of 150 mm. cubes at 28 days curing after mixing & tests conducted in accordance with relevant clauses of IS 456/IS 516/IRC 16/1987/IRC-78/1983 using crusher broken hard granite coarse aggregate of 10 mm. to 20mm. sizes & proportion as specified in clause-302.6.2 of IRC 21/1987, IS-10262 & subject to mix design in conformity with the grading & proportion of different materials for concrete as specified in the relevant codes of approved	47.64	One Cum	5190.79	247289.00

Handwritten signature
26.5.23

6	Supply of HYSD bars conforming to approved grade cutting bending , binding, lapping, splicing, welding etc. (conforming to ISI specification) & jointing if necessary by lapping & tying the grills & placing in position as required for RCC works as per the approved design, hoisting, lowering & laying position including cost & conveyance, Cess of tor steel & binding wires of 18 to 20 gauge (as approved by the Deptt.) etc. complete (Weight of binding wire shall not be considered for payment at all which will be borne by the contractor (standard CO-efficient of different size of the steel shall be considered & welding & lapping should conform to relevant clause of IRC - 21/1987) as per direction of the Engineer in charge.				
		52.40	One Qtl	8,838.18	463121.00
7	Rigid smooth centering shuttering for R.C.C.work including all cost etc complete				
A	Cut off wing wall	239.58	One Sqm	102.73	24612.00
B	Column	81.18	One Sqm	749.32	60830.00
C	Roof Slab Hall	32.37	One Sqm	436.09	14116.00
8	16 mm thick grading plaster (1:6) finished smooth on roof slab including, watering and curing with cost and conveyance of all materials and labour, cess with T&P required for the work with all taxes and royalties , Cess etc. complete in all respect in all floors as per direction of the Engineer in charge.				
		54.90	One Sqm	206.18	11319.00
9	Earth work in excavation of foundation in hard or gravel soil with initial lead and lifts including dressing and leveling the bed and depositing the excavated earth at places away from work site with all leads and lifts including cost of all labour, cess and T&P and dewatering if required for the work etc. Complete as directed by the Engineer-in charge				
		335.22	One Sqm	165.65	55529.00
Total estimated cost in Figures					1753496.00
Or say Total Estimated Cost Put up for Tender					Rs. 17,53,496.00
Quoted Amount					
Quoted rate in Words					

I Mr/Mrs/Ms.....Class of

NOTE

- 1.The Contractor should not wright anything except Quoting of percentage and in case anything else regarding
- 2.Strike out which is not applicable
- 3.Percentage should be Quoted up to two(02) digit after the decimal point

Nos. Of Correction.....
 Nos. Of Over Writting.....
 Nos. Of Pages Submitted.....

Assistant Exexutive Engineer
 K.Nuagaon Block

Jawal
 26.9.23
 Block Development Officer
 K.Nuagaon Block