



PANCHAYAT SAMITI OFFICE, G.UDAYAGIRI

G.UDAYAGIRI, DIST. - KANDHAMAL, ODISHA, PIN - 762100

Telephone - 06847-260040/ 260540 (FAX), e-mail - [ori-gudayagiri@nic.in](mailto:ori-gudayagiri@nic.in)

Letter No. -

49

Date:

04.01.2020

To

The District Information Officer,  
NIC, Kandhamal, Phulbani.

Sub:- Uploading of Tender call notice.

Sir

With reference to the subject cited above I am to say that, a tender notice is invited from intending bidders for construction. In enclosing herewith the Tender call notice, Tender Paper in PDF format along with hard copy you are requested to upload in the [kandhamal.nic.in](http://kandhamal.nic.in) website. The tender opening dated is **17.01.2020** for the following project.

1. Construction of BDO quarter at G.Udayagiri Block premises.
2. Construction of Block Conference Hall at G.Udayagiri Block.
3. Construction of Room-cum-Gallery, Toilets and Mini Halls for Block Level Mini-Stadium, Rattingia

This is for your kind information and necessary action.

Yours faithfully

  
Block Development Officer  
G.Udayagiri

4/1/2020

**GOVERNMENT OF ODISHA**  
**OFFICE OF THE PANCHAYAT SAMITI, G.UDAYAGIRI**  
**DIST. KANDHAMAL, PIN-762100**  
**INVITATION FOR BIDS (IFB)**

No. 45

Date: 04.01.2020

1. The Block Development Officer, G.Udayagiri, Dist. Kandhamal on behalf of Governor of Odisha invites Percentage rate bids in Single Cover System for construction of civil works as detailed below from eligible contractor registered with State Government/ Central Government/ M E S / Railways for which agreement to be drawn up in the standard P.W.D. P-1 Agreement Format


Sl. No	Name of work	Approximate value of work (in Rs)	Security (E.M.D 1%) (in Rs.)	Cost of Tender Paper (in Rs.)	Class of Contractor	Period of completion
1	2	3	4	5	6	7
1	Construction of BDO quarter at G.Udayagiri	1326928/-	13269/-	6000/- (Non refundable)	'C' or 'B' Class	06 (Six) calendar months
2	Construction of Block Conference Hall at G.Udayagiri	2093646/-	20936/-	6000/- (Non refundable)	'C' or 'B' Class	06 (Six) calendar months
3	Construction of Room-cum-Gallery, Toilets and Mini Halls for Block Level Mini-Stadium, Rattangia	1951165/-	19511/-	6000/- (Non refundable)	'C' or 'B' Class	06 (Six) calendar months

2. The sale of Tender paper will be started from **07.01.2020 To 16.01.2020 (excluding holidays)** in office hour.
3. Bidders submitting downloaded bid documents from official website [www.kandhamal.nic.in](http://www.kandhamal.nic.in) are requested to deposit the requisite non-refundable fees as mentioned in Column No 5 in shape of demand draft prepared on or before last date of sale of tender paper and submit the same along with the bid keeping in a separate envelope marks "Cost of tender documents" downloaded from the internet or else tender paper will be rejected.
4. The sealed bid documents will be received from **07.01.2020 To 16.01.2020 (excluding holidays)** up to 10.00 AM by dropping the sealed bid documents in the Tender Box having identification No- PSGUD-02 / 2019-20 put in the Office of the B D O, G Udayagiri, Dist. Kandhamal. The Tender Paper received after the stipulated time will not be considered.
5. All the bids received by the office will be opened on dated **17.01.2020 at 11.00 AM** in the Office of the undersigned in presence of Tender Committee and Bidders or the Authorized Representatives of bidders.
6. For other details you can visit the website [www.kandhamal.nic.in](http://www.kandhamal.nic.in) or in the office of the BDD, G.Udayagiri during office hour.

  
 Block Development Officer  
 G.Udayagiri, Dist. Kandhamal

Memo No. 46 Dtd. 04.01.2020

Copy forwarded to the Editor DHARITRI / SAMABAD (Odia daily) for information with request to get it published in shortest space possible within the amount of Rs. 11 000/- (Eleven Thousand) at an early date for wide circulation of Invitation of Bids. The complimentary copy of News papers containing Tender Call Notice may be sent to this office for reference & record

  
 Block Development Officer  
 G.Udayagiri, Dist. Kandhamal


Memo No. 47 Dtd. 04.01.2020

Copy submitted to the Collector & Dist. Magistrate, Kandhamal, Phullabani for favour of kind information

  
 Block Development Officer  
 G.Udayagiri, Dist. Kandhamal

Memo No. 48 Dtd. 04.01.2020

Copy submitted to Project Director, DRDA, Kandhamal/ all BDOs of Kandhamal Dist./ Executive Engineers, R&B/ RWSS/ M.I./ R.D. Balliguda & Phullabani, D.I. & P.R.O. Phullabani for information and wide circulation with a request to display the Tender Call Notice on their Notice Board.

  
 Block Development Officer  
 G.Udayagiri, Dist. Kandhamal

**TENDER SCHEDULE ( BILL OF QUANTITIES )**

**Name of work- Construction of Block Conference Hal, G.Udayagiri**

**Estimated cost - Rs - 25,00000 /-**

SI No	Item of work	Qty	Unit	Rate	Amount
1	Earth work in excavation in foundation in all kinds of soil including hard moorum, stony earth mixed with boulders (except sheet rock & boulders requiring blasting) with all leads and lifts including dressing and leveling the bed and depositing the excavated earth at place away from work site with all leads and lifts including cost of all labour and T&P and dewatering if required for the work etc. complete and as directed by the Engineer-in-charge.	70.55	cum	177.31	12509.00
2	Supplying filling in foundation and plinth with sand in 23.5cm(9") thick layers including watering and ramming with the cost conveyance royalties taxes of the materials and labour with T&P required for the work etc. complete (Measurement will be taken on finished compacted section only.)	50.40	cum	425.30	21435.00
3	Cement concrete of proportion (1:4:8) with 4cm size hard granite metal 1cum including cost conveyance ,royalty & all other taxes of materials etc complite as per direction of E C I.	24.13	cum	3990.70	96296.00
4	Fly ash brick masonry in cement mortar 1:4 after immersing bricks for six hours in water before use in superstructure using clamp burnt bricks of 9"/10" size having a crushing strength of not less than 50 kg per sq.cm including splays cutting, circular molding chamfering and corbelling and similar such type of works with all necessary projections watering and curing etc. complete including cost and conveyance of all materials and labour , T&P required for the work with all taxes and royalties etc. complete in all respect .	23.64	cum	4698.72	111078.00
5	R C C work of grade M-20having a minimum compressive strength inwork text of 200kg/cm in15cm cubes at 28days after mixing and tests conducted using 10mm to 20mm size (20mm not to exceed 25percents)crusher black broken granite stone chips of approved quality and from approved quarry including hoisting lowering and laying concrete by using vibrators watering and curing for four weeks centering and shuttering and finishing the exposed surface smooth to receive painting or white or colour washing providing grooves or beads where necessary including cost conveyance taxes and royalty of all materiala and labour required for the works etc complit with all T&p and cess in all respect but exeluding cost of rain forcement M S rods or tor steel and binding wires of 18to20 guage and labour charges etc .completes as per specification and direction of EIC.	49.34	cum	4975.80	245506.00
6	Straightening bent up or coiled rods cutting bending cranking hooking welding or jointing (if required) the M.S.Rods or Tor Steel with binding wires and binding tying the grills, hoisting, lowering & placing in proper position as required for all types of R.C.C. works including cost, conveying royalties & taxes of M.S. rods or Tor steel and binding wires of 18 to 20 gauge and labour with T&P required for the work etc. complete in all floors ( weight of binding wires will not be considered for payment , and payment will be made on weight of M S rods or Tor steel only	45.00	qntl	5277.64	237494.00

CONTRACTOR

  
 Block Development officer  
 G Udayagiri

7	20mm (3/4") thick grading plaster with cement mortar (1:4) over roof slab after chipping and chiseling the same and cleaning the surface by wire brushing laid to proper slope finished smooth to receive tarfelt treatment watering and curing including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors.	173.83	Sqm	215.93	37535.00
8(a)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(foundation)	31.93	Sqm	105.80	3378.00
8(b)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(lintal&chaja)	17.79	sqm	263.59	4689.00
8(c)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(column & Beams)	146.62	sqm	706.74	103622.00
8(d)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(Roof)	181.99	sqm	416.19	75742.00
9	Fly ash brick masonry in cement mortar 1:6 after immersing bricks for six hours in water before use in superstructure using clamp burnt bricks of 9"/10" size having a crushing strength of not less than 50 kg per sq.cm including splays cutting, circular molding chamfering and corbelling and similar such type of works with all necessary projections watering and curing etc. complete including cost and conveyance of all materials and labour , T&P required for the work with all taxes and royalties etc. complete in all respect .	49.64	cum	4541.57	225444.00
10	16mm (5/8") thick cement plaster (1:6) finished smooth to inside surface of 9"/10" thick brick walls after raking out joints including watering and curing with the cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete.	276.53	Sqm	194.85	53882.00
11	12mm (1/2") thick cement plaster (1:6) finished smooth to out side brick walls after raking out joints including watering and curing with cost and conveyance, of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors.	212.94	Sqm	137.66	29313.00
12	Fixing tiles in floor tradesor steps and landing on 25mm thick cement mortar(1:1)jointed with neat cement slurry mixing with pimentsto match the sade of the tiles including Rubbing &polishing complete including cost of pre cast tiles per 1sqm Data for 10 sqm	141.44	Sqm	1249.17	176682.00

CONTRACTOR



Block Development officer  
G Udayagiri

13	Providing, fitting and fixing of Kota tiles of approved quality, thickness and sizes in dadoes skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing, polishing to finished smooth, watering, curing with cost conveyance, royalties taxes of all materials, all labour, T&P required for the work etc. complete in all respect as per the direction of Engineer .in-charge.	38.42	Sqm	1036.25	39813.00
14	Providing fitting,fixing of AL door with anodized AL. door section of 9202 as vertical member,9201 as top,9200 as bottom and middle member with frame section as 9221 with tapered clip No.4660 and the frame to be completed by means of jointed angle No.1855 including all cost of labour,T&P,hire charges of drilling machine,labour charges atc,complete including cost of laminated board.	73.51	Kg	492.66	36216.00
15	Supplying,fitting,fixing up window (sliding type) made up aluminium Section 9778 as windows frame,section No.4095,4096 and 9777,3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all tyes labour, T&P including cost of glass etc,complete as per direction of Engineer-in-charge.	43.57	Kg	727.01	31676.00
16	Cost of MS doors and windows with angle iron frames & grills of approved design including cost, conveyance, taxes etc complete.	396.00	Kg	85.00	33660.00
17	Cost of fiber door.	4.88	Sqm	1450.00	7076.00
18	Painting two coats with any approved paint over a coat of priming to new woodwork and ironwork including cost of primer and paint, sand papering polishing the surface with cost conveyance taxes of all materials and labour with T&P required for the work etc. complete in all respect.	22.02	Sqm	187.92	4138.00
19	Finishing walls with water proofing cement paint two coats of approved shade including cost of weather coat for new works	212.94	Sqm	33.43	7119.00
20	Finishing wall surface ofwalls with Acylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting	347.53	Sqm	27.52	9564.00
21	Destepering two coats to wall with distemper of approved shade on new work to give an even shade excluding cost of distemper per 1 sqm.	347.53	Sqm	64.45	22398.00
22	Providing fitting and fixing of fales ceiling with Aluminium anodised T Section No.3215 with 2'-0"center to center, L section No.1705 upto 15 micron on 4 walls to be fixed by means of steel screw and PVC plug and the Aluminium grid 2'-0" X 2'-0" suspended from ceiling etc complete.	120.40	Sqm	1,385.81	166852.00
23	Const. of Display board	L	S		Rs. 3,529.00
24	Provision for GST				Rs. 2,97,000.00
				<b>Total</b>	<b>2093646.00</b>

Total Twenty four (24) item only

(Rupees Twenty lakhs nintythree thousand six hundred fourtysix) only

Percentage excess / less

- (a) In figures .....% excess  
(b) In words .....% excess  
(c) In figures .....% less  
(d) In words .....% less

Total No of correction :

Total No of overwriting :

Total No of interpolation :

CONTRACTOR



Block Development officer  
G Udayagiri

**TENDER SCHEDULE ( BILL OF QUANTITIES )**

**Name of work- Const. of mini stadium at Ratingia**

**Estimated cost - Rs - 20,00000 /-**

Sl No	Item of work	Qty	Unit	Rate	Amount
1	Earth work in excavation in foundation in all kinds of soil including hard moorum, stony earth mixed with boulders (except sheet rock & boulders requiring blasting) with all leads and lifts including dressing and leveling the bed and depositing the excavated earth at place away from work site with all leads and lifts including cost of all labour and T&P and dewatering if required for the work etc. complete and as directed by the Engineer-in-charge.	114.23	cum	177.31	20254.00
2	Supplying filling in foundation and plinth with sand in 23.5cm(9") thick layers including watering and ramming with the cost conveyance royalties taxes of the materials and labour with T&P required for the work etc. complete (Measurement will be taken on finished compacted section only.)	24.18	cum	425.30	10284.00
3	Cement concrete of proportion (1:4:8) with 4cm size hard granite metal 1cum including cost conveyance ,royalty & all other taxes of materials etc complite as per direction of E C I.	19.44	cum	3986.88	77505.00
4	Fly ash brick masonry in cement mortar 1:4 after immersing bricks for six hours in water before use in superstructure using clamp burnt bricks of 9"/10" size having a crushing strength of not less than 50 kg per sq.cm including splays cutting, circular molding chamfering and corbelling and similar such type of works with all necessary projections watering and curing etc. complete including cost and conveyance of all materials and labour , T&P required for the work with all taxes and royalties etc. complete in all respect .	20.34	cum	4541.61	92376.00
5	R C C work of grade M-20having a minimum compressive strength inwork text of 200kg/cm in15cm cubes at 28days after mixing and tests conducted using 10mm to 20mm size (20mm not to exceed 25percents)crusher black broken granite stone chips of approved quality and from approved quarry including hoisting lowering and laying concrete by using vibrators watering and curing for four weeks centering and shuttering and finishing the exposed surface smooth to receive painting or white or colour washing providing grooves or beads where necessary including cost conveyance taxes and royalty of all materiala and labour required for the works etc complit with all T&p and cess in all respect but excludng cost of rain formement M S rods or tor steel and binding wires of 18to20 guage and labour charges etc .completes as per specification and direction of EIC.	80.56	cum	4948.12	398621.00
6	Straightening bent up or coiled rods cutting bending cranking hooking welding or jointing (if required) the M.S.Rods or Tor Steel with binding wires and binding tying the grills, hoisting, lowering & placing in proper position as required for all types of R.C.C. works including cost, conveying royalties & taxes of M.S. rods or Tor steel and binding wires of 18 to 20 gauge and labour with T&P required for the work etc. complete in all floors ( weight of binding wires will not be considered for payment , and payment will be made on weight of M S rods or Tor steel only	85.10	qntl	5278.51	449201.00
7	20mm (3/4") thick grading plaster with cement mortar (1:4) over roof slab after chipping and chiseling the same and cleaning the surface by wire brushing laid to proper slope finished smooth to receive tarfelt treatment watering and curing including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors.	7.62	Sqm	212.05	1616.00
8(a)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(foundation)	59.78	Sqm	105.80	6325.00
8(c)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(column & Beams)	281.28	sqm	706.74	198792.00

CONTRACTOR

  
 Block Development officer  
 G Udayagiri

8(d)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dables away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(Roof)	149.48	sqm	416.19	62212.00
9	Fly ash brick masonry in cement mortar 1:6 after immersing bricks for six hours in water before use in superstructure using clamp burnt bricks of 9"/10" size having a crushing strength of not less than 50 kg per sq.cm including splays cutting, circular molding chamfering and corbelling and similar such type of works with all necessary projections watering and curing etc. complete including cost and conveyance of all materials and labour , T&P required for the work with all taxes and royalties etc. complete in all respect .	52.60	cum	4384.45	230622.00
10	16mm (5/8") thick cement plaster (1:6) finished smooth to inside surface of 9"/10" thick brick walls after raking out joints including watering and curing with the cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete.	159.72	Sqm	191.34	30561.00
11	12mm (1/2") thick cement plaster (1:6) finished smooth to out side brick walls after raking out joints including watering and curing with cost and conveyance, of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors.	464.03	Sqm	134.73	62519.00
16	Cost of MIS doors and windows with angle iron frames & grills of approved design including cost, conveyance, taxes etc complete.	480.00	Kg	85.00	40800.00
18	Painting two coats with any approved paint over a coat of priming to new woodwork and ironwork including cost of primer and paint, sand papering polishing the surface with cost conveyance taxes of all materials and labour with T&P required for the work etc. complete in all respect.	5.16	Sqm	187.92	970.00
19	Finishing walls with water proofing cement paint two coats of approved shade including cost of weather coat for new works	464.03	Sqm	33.43	15513.00
20	Destepering two coats to wall with distemper of approved shade on new work to give an even shade excluding cost of distemper per 1 sqm.	176.79	Sqm	64.45	11394.00
21	Const. of Display board	L	S		Rs. 4,000.00
22	Provision for GST		12%		Rs. 2,37,600.00
				<b>Total</b>	<b>1951165.00</b>

Total Twenty two (22) item only

(Rupees Ninteen lakhs fiftyone thousand one hundrad sixtyfive) only

Percentage excess / less

- (a) In figures .....% excess  
(b) In words .....% excess  
(c) In figures .....% less  
(d) In words .....% less

Total No of correction :

Total No of overwriting :

Total No of interpolation :

CONTRACTOR

  
Block Devlopment officer  
G Udayagiri

**TENDER SCHEDULE ( BILL OF QUANTITIES )**

**Name of work- Construction of BDO quarter**

**Estimated cost - Rs - 14,00000 /-**

SI No	Item of work	Qty	Unit	Rate	Amount
1	Earth work in excavation in foundation in all kinds of soil including hard moorum, stony earth mixed with boulders (except sheet rock & boulders requiring blasting) with all leads and lifts including dressing and leveling the bed and depositing the excavated earth at place away from work site with all leads and lifts including cost of all labour and T&P and dewatering if required for the work etc. complete and as directed by the Engineer-in-charge.	55.73	cum	177.31	9881.00
2	Supplying filling in foundation and plinth with sand in 23.5cm(9") thick layers including watering and ramming with the cost conveyance royalties taxes of the materials and labour with T&P required for the work etc. complete (Measurement will be taken on finished compacted section only.)	27.90	cum	425.30	11866.00
3	Cement concrete of proportion (1:4:8) with 4cm size hard granite metal 1cum including cost conveyance ,royalty & all other taxes of materials etc complite as per direction of E C I.	15.26	cum	4036.36	61595.00
4	Fly ash brick masonry in cement mortar 1:4 after immersing bricks for six hours in water before use in superstructure using clamp burnt bricks of 9"/10" size having a crushing strength of not less than 50 kg per sq.cm including splays cutting, circular molding chamfering and corbelling and similar such type of works with all necessary projections watering and curing etc. complete including cost and conveyance of all materials and labour , T&P required for the work with all taxes and royalties etc. complete in all respect .	23.44	cum	4620.84	108312.00
5	R C C work of grade M-20having a minimum compressive strength inwork text of 200kg/cm in15cm cubes at 28days after mixing and tests conducted using 10mm to 20mm size (20mm not to exceed 25percents)crusher black broken granite stone chips of approved quallity and from approved quarry including hoisting lowering and laying concrete by using vibrators watering and curing for four weeks centering and shuttering and finishing the exposed surface smooth to receive painting or white or colour washing providing grooves or beads where necessary including cost conveyance taxes and royalty of all materiala and labour required for the works etc complit with all T&p and cess in all respect but excludng cost of rain forcement M S rods or tor steel and binding wires of 18to20 guage and labour charges etc .completes as per specification and direction of EIC.	30.29	cum	4919.26	149004.00
6	Straightening bent up or coiled rods cutting bending cranking hooking welding or jointing (if required) the M.S.Rods or Tor Steel with binding wires and binding tying the grills, hoisting, lowering & placing in proper position as required for all types of R.C.C. works including cost, conveying royalties & taxes of M.S. rods or Tor steel and binding wires of 18 to 20 gauge and labour with T&P required for the work etc. complete in all floors ( weight of binding wires will not be considered for payment , and payment will be made on weight of M S rods or Tor steel only	27.90	qntl	5277.64	147246.00

CONTRACTOR

  
 Block Development officer  
 G Udayagiri

7	20mm (3/4") thick grading plaster with cement mortar (1:4) over roof slab after chipping and chiseling the same and cleaning the surface by wire brushing laid to proper slope finished smooth to receive tarfelt treatment watering and curing including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors.	98.68	Sqm	213.95	21113.00
8(a)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(foundation)	31.32	Sqm	105.80	3314.00
8(b)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(lintal&chaja)	20.88	sqm	263.59	5504.00
8(c)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(column & Beams)	78.32	sqm	706.74	55352.00
8(d)	Rigid smooth centering and shuttering for R C C works including cost of all materials and binding wires and depositing the dabries away from working area after dismantalling the same ,complete as per specification and direction of Engineer in charge(Roof)	107.00	sqm	416.19	44532.00
9	Fly ash brick masonry in cement mortar 1:6 after immersing bricks for six hours in water before use in superstructure using clamp burnt bricks of 9"/10" size having a crushing strength of not less than 50 kg per sq.cm including splays cutting, circular molding chamfering and corbelling and similar such type of works with all necessary projections watering and curing etc. complete including cost and conveyance of all materials and labour , T&P required for the work with all taxes and royalties etc. complete in all respect .	36.47	cum	4463.68	162790.00
10	16mm (5/8") thick cement plaster (1:6) finished smooth to inside surface of 9"/10" thick brick walls after raking out joints including watering and curing with the cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete.	293.70	Sqm	193.15	56728.00
11	12mm (1/2") thick cement plaster (1:6) finished smooth to out side brick walls after raking out joints including watering and curing with cost and conveyance, of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors.	125.80	Sqm	136.25	17140.00
12	Fixing tiles in floor tradesor steps and landing on 25mm thick cement mortar(1:1)jointed with neat cement slurry mixing with pimentsto match the sade of the tiles including Rubbing &polishing complete including cost of pre cast tiles per 1sqm Data for 10 sqm	75.25	Sqm	1192.15	89710.00

CONTRACTOR

  
 Block Development officer  
 G Udayagiri

13	Providing, fitting and fixing of Kota tiles of approved quality, thickness and sizes in dadoes skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing, polishing to finished smooth, watering, curing with cost conveyance, royalties taxes of all materials, all labour, T&P required for the work etc. complete in all respect as per the direction of Engineer .in-charge.	26.65	Sqm	1034.84	27578.00
14	Providing fitting,fixing of AL door with anodized AL. door section of 9202 as vertical member,9201 as top,9200 as bottom and middle member with frame section as 9221 with tapered clip No.4660 and the frame to be completed by means of jointed angle No.1855 including all cost of labour,T&P,hire charges of drilling machine,labour charges atc,complete including cost of laminated board.	9.10	Kg	4500.00	40969.00
15	Supplying,fitting,fixing up window (sliding type) made up aluminium Section 9778 as windows frame,section No.4095,4096 and 9777,3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all tes labour, T&P including cost of glass etc,complete as per direction of Engineer-in-charge.	40.85	Kg	727.01	29698.00
16	Cost of MS doors and windows with angle iron frames & grills of approved design including cost, conveyance, taxes etc complete.	407.00	Kg	85.00	34595.00
17	Cost of fiber door.	3.25	Sqm	1500.00	4875.00
18	Painting two coats with any approved paint over a coat of priming to new woodwork and ironwork including cost of primer and paint, sand papering polishing the surface with cost conveyance taxes of all materials and labour with T&P required for the work etc. complete in all respect.	13.17	Sqm	187.92	2475.00
19	Finishing walls with water proofing cement paint two coats of approved shade including cost of weather coat for new works	125.80	Sqm	33.43	4205.00
20	Destepering two coats to wall with distemper of approved shade on new work to give an even shade excluding cost of distemper per 1 sqm.	377.08	Sqm	64.45	24303.00
21	Providing fitting and fixing of fales ceiling with Aluminium anodised T Section No.3215 with 2'-0"center to center, L section No.1705 upto 15 micron on 4 walls to be fixed by means of steel screw and PVC plug and the Aluminium and 2'-0" X 2'-0" suspended from ceiling etc complete.	35.67	Sqm	1,228.56	43823.00
22	Const. of Display board	L	S		Rs. 4,000.00
23	Provision for GST	12%			Rs. 1,66,320.00
				<b>Total</b>	<b>1326928.00</b>

Total Twenty three (23) item only

(Rupees thirteen lakhs twentysix thousand nin hundred twentyeight) only

Percentage excess / less

- (a) In figures .....% excess  
(b) In words .....% excess  
(c) In figures .....% less  
(d) In words .....% less

Total No of correction :

Total No of overwriting :

Total No of interpolation :

CONTRACTOR

  
Block Development officer  
G Udayagiri